

THANE MUNICIPAL CORPORATION

SCHEDULE - B

9

Name of Work : Construction Of Gutter & Footway From Niligeeeri Chwal To Nobel House In Ward No. 62.

SR.NO.	DESCRIPTION	Quantity	Rate	Per	Amount
1	Dismantling R.C.C. concrete work including breaking concrete by chiselling, wedging etc. including cutting the reinforcement, stacking the serviceable materials and the debris separately upto a distance of 50 metre or spreading the debris as directed etc. complete.				
	T.D.S.R.2013-14/Item no.51/page no.121	6.48	392.70	Cu.M	2544.70
2	Dismantling carefully the existing plain concrete, including stacking the materials neatly within 50 meter lead as directed etc. complete.				
	T.D.S.R.2013-14/Item no.50/page no.121	12.96	304.50	Cu.M	3946.32
3	Excavation for foundation/pipe trenches in ash muddy/ marshy/ slushy/soil incld. Use of poclain, labour for dewatering during execution incld. Removing the excavated material upto a distance of 50 m & lifts as below, stacking & spreading as directed, etc complete.				
	M.J.P. D.S.R. 2012-2013	19.44	310.65	Cu.M	6039.04
4	Excavation for foundation in soft including removing the excavated materials upto a distance of 50 meters beyond the building area etc.complete..				
	T.D.S.R.2013-14/Item no.1(a)/page no.6	137.37	109.20	Cu.M	15000.80
5	Providing dry trap/rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.				
	T.D.S.R. 2013-14/Item no.6/ pg.no.7	72.03	525.00	Cu.M	37815.75
6	Providing & laying in situ cement concrete in proportion of trap metal for foundation and bedding, including bailing out water manually, fornwork, compacting & curing etc.complete.				
	T.D.S.R. 2013-14/Item no.1(c)/ pg.no.15 1:3:6	42.765	3766.98	Cu.M.	161094.90
7	Providing and casting in situ cement concreteM-15 of trap metal for bed block, foundation blocks and such other items, including bailing out water manually, etc. complete.				
	T.D.S.R.2013-14/ Item no.4(a) / page no.16	23.184	4427.85	Cu.M.	102655.27

8	Providing and Fixing in position M.S./H.Y.S.D./T.M.T. bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns canopies Etc. complete.				
	T.D.S.R.2013-14/Item no.11(b)/page no.20	0.63862	64493.63	M.T.	41186.66
9	Providing and casting in situ cement concrete M-20 of trap metal for R.C.C. Slab and landing upto and inclusive of 15 cm. thickness as per Etc. complete.				
	T.D.S.R.2013-14 / IT. NO. 5(A)a /PG.NO.18	9.504	7146.30	Cu.M	67918.44
10	P/Pre-cast SFRC rectangular chamber covers of size.....(0.9 m x 0.70 x.04)m opening (0.9x0.6)m with frame ,made out of steel fibre composite concrete of M35 grade as per ASTM standard and generally conforming to IS 12592 with 28 days curing.				
	MJP DSR :-2012-2013 /It.No..17(d)/Pg.No.263	24.00	2906.20	Nos.	69748.80
11	Providing and fixing cement concrete RCC sleeper slab (Dhapas) of M30 of trap metal above 12.5 cm and upto and inclusive of 15cm thick as per detailed designs and drawings or as directed including centering, formwork, compacting, roughing the surface in specific finish is to be provided and curing (excluding reinforcement)				
	Rate Analysis	102.00	750.00	Nos.	76500.00
12	Providing and laying in position polished Shahabad Stone flooring 30 cm. x 30 cm. of approved quality 25mm to 30mm thick in plain/diamond pattern etc. complete.				
	Rate Analysis	285.10	1361.00	Sqmt.	388021.10
13	Transportation of excavated materials upto 5km.etc complete				
	T.D.S.R.2013-14 /Statement C/ Page No. 198	127.263	200.04	Cum	25457.69
					997929.47
				SAY RS.	998000.00